



**NOTES :**

1. ALL EXCAVATIONS WITHIN COUNTY RIGHT-OF-WAY SHALL REQUIRE AN EXCAVATION PERMIT FROM THE ROAD PERMIT SECTION.
2. ROAD PERMITS ARE NOT VALID WITHOUT FULL COMPLIANCE OF UNDERGROUND SERVICE ALERT REQUIREMENTS.
3. ALL EXCAVATIONS SHALL BE CONSTRUCTED AS PRESCRIBED BY CAL. OSHA.
4. TEMPORARY PAVING SHALL BE 0.17' THICK, COMPACTED SMOOTH AND FLUSH, AND SHALL BE PLACED IN ALL AREAS PAVING WAS REMOVED PRIOR TO OPENING TO TRAFFIC AND AT THE END OF EACH DAY(SEE SECTION 8.1).
5. COMPACTION TESTS IN THE 90% RC PIPE ZONE SHALL BE ON 250' INTERVALS AND SUBMITTED TO INSPECTION PRIOR TO PERMANENT PAVING.
6. NOTIFY PERMIT INSPECTOR TWO WORKING DAYS PRIOR TO STARTING A PROJECT AND FOR EACH PHASE OF CONSTRUCTION.
7. OVERLAY PAVING SHALL COMPLY WITH SECTION 8.5.

T-GRIND TRENCH

TRENCH DETAIL

B